

ATTACHMENT A

840 ST. GEORGE STREET



Columns are undersized and not founded on proper foundations.

Beam is spliced mid-span on both members, relying solely on the shear strength of the fasteners.

ATTACHMENT A

840 ST. GEORGE STREET



Joists are improperly installed with screws instead of nails. Screws have very little shear value.



2-ply beam spliced incorrectly with deck screws.

