


# ATTACHMENT F

## URBAN COLLECTOR CROSS SECTION



### NOTES:

1. PAVED SURFACE - 100mm ASPHALT (COMPACTED THICKNESS)
2. BASE - 150mm AS PER SECTION 9
3. SUB-BASE - 250mm AS PER SECTION 9
4. BARRIER CURB AND GUTTER TO BE USED IN ACCORDANCE WITH STANDARD DRAWING CS-1.
5. POCKET PARKING DELINEATION CURB TO BE OPTIONAL UNLESS PARKING HAS BEEN DESIGNED WITH A REVERSE CROSSFALL. ROLLOVER OR VALLEY CURB TO BE USED AS GRADE BREAK FOR DRAINAGE PURPOSES.
6. DEPTHS OF SURFACING AND BASE GRAVELS ARE MINIMUM AND IN SOME CASES WILL HAVE TO BE INCREASED TO MEET MAXIMUM ALLOWABLE BENKELMAN BEAM DEFLECTION.
7. FLEX ZONE TO BE UTILIZED FOR: LANDSCAPING, STREET TREES, POCKET PARKING, TRANSIT STOPS, BUS SHELTERS, BIKE PARKING, FURNITURE, UTILITY BOXES/CABINETS, HYDRANTS, POWER POLES, STREETLIGHTS, STORMWATER MANAGEMENT, OR WASTE RECEPTACLES.
8. BANDING/BUFFER ON EITHER SIDE OF THE BIKE PATH SHALL BE 0.3m STAMPED CONCRETE WITH TRANSVERSE SCORE LINES AT 0.3m INTERVALS. WHERE VERTICAL SEPARATION IS PREFERRED, MOUNTABLE MONOLITHIC CURB MAY BE UTILIZED. ALTERNATIVE TREATMENTS TO BE APPROVED BY THE CITY ENGINEER.
9. POCKET PARKING DOOR ZONES OR OTHER HARD SURFACES TO USE COLOURED AND/OR STAMPED CONCRETE.
10. ROAD HAS CONTROLLED ACCESS. ACCESS UNDER APPROVAL FROM CITY ENGINEER.
11. CROSS-SECTIONS TO BE USED IN CONJUNCTION WITH CITY'S COMPLETE STREET DESIGN GUIDELINES.
12. STREETLIGHTS ARE DIAGRAPHIC. LIGHTING LEVELS TO BE IN ACCORDANCE WITH SECTION 10.
13. LANDSCAPING TO BE IN ACCORDANCE WITH SECTION 14.

G:\INFRASTRUCTURE PLANNING\STANDARDS & PRODUCTS\SMO\SECTION 10\13 MAY 2020\2020-05-01 FINAL MOESS EDITION NO13 DOCUMENT 2020 DRAWING SECTIONS\SECTION 8 DWGS\UC-XS2

7.3.2020



STREET TYPES & CROSS SECTIONS  
URBAN COLLECTOR

Scale: NTS  
Created: AUG 2019  
Rev Date: MAY 2020  
Dwg No: UC-XS2